## **Erosion & Sediment Control for Linear Utility Operations**

Ted Sherrod, PE, CPESC, CPSWQ, CPMSM AECOM — Raleigh <a href="mailto:Ted.sherrod@aecom.com">Ted.sherrod@aecom.com</a>






### TED'S TOP TEN

- 10. Never place temp E&SCs in jurisdictional streams or wetlands, unless...
  - 9. Consider turbidity curtains where water impoundments occur downstream
  - 8. Detail management of OTHER construction site pollutants
  - 7. Avoid long runs of silt fence w/out designed breaks/outlets w/sed traps
  - 6. Insist on adequate LOD for staging/stockpiling areas & sediment storage
  - 5. All basins/traps require coir fiber baffles
  - 4. Detail anchor trenching on erosion control matting
  - 3. Specify biodegradable rolled or hydraulic EC product in ESAs
  - 2. Utilize PAMs to provide additional treatment for turbidity reduction
  - 1. Plan to address Inadvertent Returns from Horizontal Directional Drilling

### Objectives

- Build Margin into the E&SC Plan Design
- Emphasis on protection at Environmentally Sensitive Areas (ESAs)



# Environmentally Sensitive Areas (ESAs)

- Areas requiring special protection during construction
- Designate the ESA with a 50' "MARGIN" on each side of resource

- Wetlands
- Surface Waters
  - Streams
  - Ponds
  - Lakes
- Riparian Buffers
- High Quality Waters (HQW)
- Outstanding Resource Waters (ORW)
- Water Supply Watersheds (WSW)
- Trout (Tr) Buffer Zones
- Critical Areas (CA)
- Section 303(d) Waters listed for Turbidity Impairment
- Coastal Areas of Environmental Concern (AEC)
- Threatened and Endangered (T&E) Species and Habitat

### Terminology

- Construction stormwater management
  - Implementation of temp & perm erosion & sediment control BMPs during the construction phase of a project
- Erosion Controls
  - BMPs that minimize the detachment phase of erosion
- Sediment Controls
  - BMPs that minimize the transport and deposition phase of erosion
- Erosion Control Plan (EC Plan) or....
   Erosion and Sediment Control Plan (E&SC Plan)



# Common E&SC Plan Implementation Issues

- Operating outside Limits of Disturbance (LOD)
- Perimeter BMP failures at ESAs (wetlands and streams)
- Insufficient BMPs to contain or control sediment on linear utility jobs



- Clearing and Grubbing
  - Only clearing, not grubbing, until immediately prior to any grading
  - Implement BMPs after clearing or concurrent with grubbing



- Temporary Stream Crossings
  - Permitted
  - Single span bridge or
  - Culverted w/clean backfill
  - Installed prior to grading



- Grading
  - Once grading begins, progress in a continuous manner until completed and stabilized...in stages
  - No start and stop or hop scotch



- Staged Seeding
  - Establish groundcover on slopes (cuts/fills)
  - No more than 10' in height measured along the slope
  - No more than one acre of exposed erodible slope area



- Seeding and Mulching/Hydroseeding
  - Immediately following final grade establishment
  - No appreciable time should lapse w/out stabilization of...
  - Slopes
  - Conveyances or
  - Other areas in the ESA

HOW ABOUT CONSTRUCTION PHASING CONSIDERATIONS?



## ESA Construction Phasing for the E&SC Plan Narrative

- Clearing and Grubbing (C&G)
  - Access Roads
  - Provide and designate adequate LOD
  - Prior to C&G, designate ESAs with highly visible flagging or fencing
  - Implement perimeter controls before and/or concurrent w/C&G
  - Regulators consider tree cutting a land disturbing operation (canopy removal)
  - Develop a C&G E&SC plan sheet(s)

## ESA Construction Phasing for the E&SC Plan Narrative

#### Grading

- Implement intermediate controls upgrade of perimeter devices
- ESA exposed areas idle for >7-14 days must be stabilized
- Provide narrative/details for
  - any dewatering of ESA work areas
  - any temporary culvert work in ESA
- Provide narrative for stockpile management
- Develop Intermediate E&SC plan sheet(s)

## ESA Construction Phasing for the E&SC Plan Narrative

- Final Grade Phase
  - Demob narrative for large sediment basins or similar
  - Coordination with any structural post-construction stormwater BMPs
  - At 70-80% perm veg phase, remove ALL temporary BMPs.... or as soon as practical
  - Develop final grade E&SC plan sheet(s)

### **E&SC** Phasing and Narrative Tips

- Notify regulator of start date and job contacts
- Avoid cut/paste
- Anticipate contractor's plan of work
- A critical component of the plan often unused as such



### BMPs allowed in ESAs

Table 3-1 - Allowed BMPs for Environmentally Sensitive Areas

- Note that EXCAVATED BMPs disallowed
- Design structural BMPs for the Q25 storm

ВМР	HQW/ORW /WSW/CA	Trout	Riparian Buffers	303(d) for Turbidity	Wetlands	T&E Species
Rock Dam	<b>√</b>	✓	✓	✓	√.	✓
Rock Dam with Sediment Trap	✓	<b>√</b>	×	✓	×	✓
Sediment Basin	<b>✓</b>	<b>✓</b>	×	<b>✓</b>	×	<b>✓</b>
Skimmer Basin	<b>✓</b>	<b>√</b>	×	<b>√</b>	×	✓
Riser Basin	✓	<b>✓</b>	×	<b>✓</b>	X	<b>✓</b>
Stilling Basin/Pumped Effluent	✓	✓	<b>√</b>	<b>√</b>	<b>√</b>	<b>✓</b>
Sediment Geotextile Bag	<b>✓</b>	✓	<b>✓</b>	<b>✓</b>	✓	<b>✓</b>
Rock Pipe Inlet Protection	✓	<b>✓</b>	✓	✓	✓	✓
Temporary Slope Drain	✓	<b>✓</b>	<b>✓</b>	<b>√</b>	✓	<b>✓</b>
Rock Inlet Protection	✓	· /	✓	✓	· /	· /
Rock Check Dam	<b>√</b>	· ✓	✓	✓	✓	· ·
Temporary Earth Berm	✓	V	<b>√</b>	✓	✓	<b>✓</b>
Temporary Silt Fence	<b>√</b>	· /	<b>√</b>	<b>√</b>	✓	<b>✓</b>
Filter Stone Fence	✓	· /	<b>√</b>	<b>√</b>	✓	✓
Filter Stone Silt Fence Breaks	✓	✓	✓	✓	✓	· /
Temporary Silt Ditch	✓	V		✓	×	<b>✓</b>
Temporary Diversion	✓	✓	×	✓	×	· ·
Wattle	✓	· /	<b>✓</b>	<b>✓</b>	✓	<b>✓</b>
Wattle Barrier	<b>✓</b>	<b>✓</b>	✓	✓	✓	<b>✓</b>
Wattle Silt Fence Breaks	<b>√</b>	<b>V</b>	<b>√</b>	<b>√</b>	✓	<b>✓</b>
Flocculants	· ·		· ·	· /	✓	

<sup>✓-</sup> BMP is allowed in this Permitted Area


<sup>-</sup> BMP is not allowed in this Permitted Area

### Wetland E&SC Design Tips


- Must be installed on ground surface
- No excavated BMPs
- Design sediment storage outside wetland boundary
- Easily removable upon project completion
- Rock allowed but completely removed



Temporary Span Bridge




### Work Zone Composite Matting



# Other ESA related E&SC Design Tips

- High Quality Waters
  - Q25; one mile and draining to project
- Trout waters and T&E aquatic listed species
  - Q25; NC trout buffer waivers; use flocculants in the design
- 303(d) Impairment for Turbidity
  - Q25; one mile and draining to project



#### BMP Implementation and Maintenance Principles

- Divert clean water
- Slow down dirty water
- Treat it...
- Impound it...
- Settle it...
- Release it...
- Maintain it



#### Hay Bales

- Not recommended on linear utility jobs!
- Undermine, bypass, deteriorating strings ....
- Superior alternative tools available in BMP Toolbox





#### Slope Breaker/Water Bar/Diversion

- Excavated "or bermed" channel that directs runoff into a sediment control structure (NOT DIRECTED TO TSF)
- Used randomly throughout project to manage runoff across open grade
- Be aware of correct tracking techniques



#### Clean Water Diversion

- Conveyance system that intercepts "clean" sheet flow up gradient of a project
- Transports clean "run on" water around the construction area and safely discharges






#### LINEAR UTILITY JOBS NEED CLEAN WATER DIVERSIONS

#### **Clean Water Diversion**


- May extend poly or fabric to top or over soil berm
- Alternative methods exist



#### **CROSS SECTION (NOT TO SCALE)**

\* Geotextile fabric should extend up and over the inside face of the berm for projects with jurisdictional trout waters.

### Temporary Clean Water Diversion



#### **Temporary Wattle Diversion**

- Option for hard to access areas or in areas with rapid phase sequencing
- Pin down and "teepee" stake to obtain good soil contact



#### Sediment Containment BMPs

- Silt Basin/Trap
- Skimmer Basin
- Rock Sediment Dam
- Coir Fiber Baffle




#### Temporary Silt Fence

- Cannot construct job with silt fence as primary sediment control
- Slope length and slope steepness are major E&SC challenges for linear construction ops



## Sediment Storage at ESAs



#### Silt Basin/Trap

- Suggest a BMP for this location
- Think back on our Imp&Mnt principles



#### Silt Basin/Trap

- Collects sediment
- Used on SFOs, water bars, locations to slow velocity, impound stormwater, and settle/store sediment
- Maintenance regularly clean out sediment at ½ design capacity








#### Silt Fence Outlets/Breaks

- Serves as a drainage break in long runs of silt fence to intercept runoff
- Provides additional sediment control in low/sag locations
- Hardware cloth w/stone or Wattles can be used in the break
- J-hooks




#### Silt Fence Break with Sediment Control Stone

- Secure overlap sections b/w silt fence and hardware cloth
- Uniform height on sediment control stone
- Install at low point or sag



#### Silt Fence Break with Wattle

- One foot overlap b/w wattle and silt fence
- Well installed wattles



#### Silt Fence Outlets (SFO)/Breaks

- All linear utility jobs w/ SFO's need sediment storage (pit/basin) and baffles
- No construction related discharge should leave job w/out basins and baffles







#### Silt Fence Outlets/Breaks

More examples of basins w/baffles at outlet locations







#### Coir Fiber Baffle

 Used to spread flow out across basin and to reduce turbulence.


Steel posts, 4' spacing, 700 g/m2 coir matting, wire support,

zip ties





#### Implementing sediment storage w/effective outlet treatment




# E&SC Strategies for Adjacent Farm Ponds


- PAM on water bar wattles
- Increase storage at SFOs
- Supplemental wattle cks with PAM
- Rock cks w/excelsior & PAM
- Intercept clean run on water
- Immediate Seeding and Mulching

- Matting on steeper slopes
- Additional easements for sediment storage
- Turbidity curtain at pond



### Supplemental E&SC design tips for downstream Ponds





Consider more aggressive
E&SCs with downstream
pond...such as PAM on water
bar wattle j-hooks; increasing
the storage at SFO; add
supplemental wattle checks w/
PAM or rock checks w/
excelsior and PAM dnstream of
SFO; immediate S&M or
matting on disturbances in this
drainage area; intercept clean
run on and pipe through
easement w/temp. corrugate
plastic pipe; Dbl TSF noted.

& INFO. MANAGEMEN (LINE 44 53+00 TH CARC

LINEAR UTILITY JOBS ENCOUNTERING CLAY .....NEED FLOCCULANT (PAM)


#### Wattles Coir / Excelsion

- Function as an alternative to rock silt checks
- Effective delivery devices for polyacrylamide (PAM)
- Requires matting underneath and proper staking





#### Wattle



#### Temporary Rock Check Dam with Matting & Flocculant

- Constructed of Class B rip-rap and #5 or #57 sediment control stone
- Uses excelsior matting to cover sediment control stone and serves as platform for flocculant application



#### Inadvertent Returns on Horizontal Directional Drilling (HDD)

Provide perimeter protection around HDD bore pits and solids





#### Inadvertent Returns (IR) on HDD Operations

Have a written IR plan to address containment, recovery, and

restoration of drilling fluids




#### Final Stabilization/Revegetation with RECPs





#### Final Stabilization/Revegetation with HECPs






#### Pulling It All Together

 What are some supplemental BMPs for this linear utility location?



#### Summary

- Follow, implement, update E&SC plan
- Attention to detail!
- Manage runoff
- Flocculants (PAM)
- Basins/Traps/Sumps w/Baffles
- Clean water diversions
- Limit amount and duration of exposure
- What is my buffer b/w work zone & watercourse?
- Maintain E&SC measures
- Achieve rapid stand of ground cover



## **Erosion & Sediment Control for Linear Utility Operations**

Ted Sherrod, PE, CPESC, CPSWQ, CPMSM AECOM — Raleigh <a href="mailto:Ted.sherrod@aecom.com">Ted.sherrod@aecom.com</a>



